

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
MAY 15 1967
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza Wichita, Kansas

Lease Name Vine "A" Well No. 2

Location NW SW NE Sec. 35 Twp. 11 Rge. 19 (E) (W) X

County Ellis Total Depth 3660

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 5 P Day 11 Month 5 Year 1967

The Above well was plugged as follows:

Total Depth 3660' 8 5/8 csg set at 241' cwc.

5 1/2 csg set at 3655' cw 100 sc cement.

Filled with sand to 3600' and dumped 5 sc cement with dump bailer.

Recov. 1485' of 5 1/2 csg.

Set rock bridge at 250' and filled to surface with readymix cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/15/67
INV. NO. 5216-W

Signed: [Signature]
Well Plugging Supervisor