



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SW NE NE

SEC. 35 TWP. 11 RGE. 19

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. A-4 Lease Vine "A"

Operator J. F. Darby Oil Co Address Box 295 Plainville, Kans

Field _____ County Ellis

Total Depth 3698 Feet.

Plugging Contractor C & G Drg Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 185' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at

600', displaced 20 sax cement through drill pipe, heavy mud to

180', set cementing plug, 1/2 sack hulls and 20 sax cement, heavy mud

to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom

cellar.

District Conservation Agent

Date 10-17-57

10-21-57
OSTZ

PLUGGING
FILE SEC. 35 TWP. 11 R. 19W
BOOK PAGE 65 LINE 32