

KANSAS

X

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Hummon Oil, Inc.

Complete Address: 821 Union Nat'l Bldg. Wichita, Kansas

Lease Name Vine "A" Well No. 2

Location 100' West of NE SW NE Sec. 35 Twp. 11 Rge. 19 (E) (W) X

County Ellis Total Depth 3755'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: H --30 Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 4 A Day 26 Month 7 Year 1968

The Above well was plugged as follows:

RTD 3755' 8 5/8 csg set at 208' cwc. Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel.
Gunned pitd, circulated heavy mud, set cementing plug at 700' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 200' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 7/29/68
INV. NO. 8195-W