

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Woodman & Iannitti Oil Company
 Complete Address P.O. Box 387 Hosington, Kansas 67544
 Lease Name Vine Well No. 1
 Location S/2 SE NW Sec. 35 Twp. 11 Rge. (E) (W) 19
 County Ellis Total Depth 3680'
 Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated
 Plugging Contractor Forbes Casing Pulling Co.
 Address Box 221 Great Bend, Kansas License No. 637
 Operation Completed: Hour 2P Day 27 Month 12 Year 1969
 The above well was plugged as follows:
Total Depth 3680' 8 5/8 csg set at 194' cwc
5 1/2 csg set at 3679 1/2' cw 100 sk cmt.
5 1/2 csg perf. (3674-3677)
Filled 5 1/2 csg W/sd (3650-3680) Dumped 5 sk cmt W/dump bailer. (3610-3650)
Cutoff and recovered 3001' of 5 1/2 csg.
Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, 70 sk cmt 6% gel,
5 sk gel, plug and 50 sk cmt W/6% gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo A. Massey
Well Plugging Supervisor

RECORDED
DEC 29 1969
WICHITA 1145-W