

KANSAS

Form CP-3
Rev. 6-4-68

f

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENCY'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 135-21388-00-00 (this well)

RECEIVED
STATE CORPORATION COMMISSION
12-27-1977
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drilling Co.

Complete Address 205 Litwin Bldg., Wichita, Kansas 67202

Lease Name Tenny "A" Well No. 1

Location NW SE NE Sec. 30 Twp. 18 Rge. (E) (W) 25

County Ness Total Depth 4406'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 11 A Day 23 Month 12 Year 1977

The above well was plugged as follows:

Total Depth 4406' 8 5/8 csg set 206' cwc 150 sk.

5 1/2 csg set 4398' cw 150 sk cem.

Filled 5 1/2 csg W/sd (4406'-4375') dumped 4 sk cem W/dump bailer. (43758-4345')

Cutoff & recovered 2545' of 5 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water- followed

with 70 sk 50-50 poz 6% gel -displaced with 10 sk gel & water & capped with

cementing plug & 50 sk 50-50 poz 6% & shutin. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED
12-27-77
6462-6

Signed: Leo Manning
Well Plugging Supervisor