

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,356-00-00 (of this well)

09-12-1977

Operator's Full Name Theodore I. Leben & Associates

Complete Address 1555 E. 2nd., Wichita, Kansas

Lease Name Humburg "A" Well No. 2

Location 670' FNL & 1970' WEL NE/4 SE C NW NE
Sec. 35 Twp. 18 Rge. (E) (W) 25

County Ness Total Depth 4493'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Abercrombie Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 3:30 A Day 10 Month 9 Year 1977

The above well was plugged as follows:

RTD 4493' 8 5/8 csg set 409' cwc 225 sk. Flg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

9-12-77
5826-W