

15-135-20361-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1970
CONSERVATION DIVISION
12-14-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company
Complete Address 617 Union Center Wichita, Kansas
Lease Name Tenny Well No. 2
Location 150' S of SE SW Sec. 19 Twp. 18 Rge. (E) (W) 25
County Ness Total Depth 4435
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Russ Casing Pulling
Address Box 1082 Great Bend, Kansas License No. 623
Operation Completed: Hour 12 N Day 11 Month 12 Year 1970

The above well was plugged as follows:

Total Depth 4435' 8 5/8 csg set at 306' cwc 200 sk.
5 1/2 csg set at 4431' cw 75 sk cmt.
Filled 5 1/2 csg W/sd (4400-4435) Dumped 5 sk cmt W/dump bailer. (4360-4400)
Cutoff and recovered 3005' of 5 1/2 csg.
Pumped down 8 5/8 csg with 28 sk gel W/5 sk hulls - 100 sk cmt 6% gel - 10 bbl
water - release plug and pumped 30 sk cmt 6% gel. Max pres. 1000 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 12/14/70
INV. NO. 3046-W