

P

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
07-07-1977
JUL 07 1977

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135-212710000 (of this well)

Operator's Full Name A. Scott Ritchie

Complete Address Suite 950, 125 North Market, Wichita, Kansas 67202

Lease Name Anspaugh Well No. 1

Location C NE SW Sec. 24 Twp. 18 Rge. (E) (W) 25

County Ness Total Depth 4390'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour _____ Day 5 Month 7 Year 1977

The above well was plugged as follows:

Total Depth 4390' 8 5/8 csg set 289' cwc 185 sk.

4 1/2 csg set 4379' cw 85 sk cmt. Top perf. (4360')

Filled 4 1/2 csg W/sd (4390'-4340') Dumped 3 sk cem W/dump bailer. (4340'-4310')

Cutoff & recovered 3730' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water -followed

with 70 sk 50-50 poz 6% -displaced with 8 sk gel & water & capped with cementing

plug & 70 sk 50-50 poz 6% & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Les Massey
Well Plugging Supervisor

DATE 7-7-77

INV. NO. 5446-4