

15-135-19121-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

AUG 18 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
08-18-1972

Operator's Full Name Palomino Petroleum  
Complete Address 304 Insurance Bldg., Wichita, Kansas 67202  
Lease Name Cook Well No. 1  
Location C SW SW Sec. 25 Twp. 18 Rge. (E) (W) 25  
County Ness Total Depth 4467'  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Glenn & Smith  
Address Box 156 Ellinwood, Kansas 67526 License No. 396  
Operation Completed: Hour 2:45 P Day 16 Month 8 Year 1972

The above well was plugged as follows:

Total Depth 4467' 8 5/8 csg set at 317' cwc 175 sk.

5 1/2 csg set at 4418' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (4400-4467) dumped 5 sk cmt W/dump bailer. (4365-4400)

Cutoff and recovered 3500' of 5 1/2 csg.

Pumped down 8 5/8 csg with 28 sk gel & water W/300 lbs hulls, -released 8 5/8 plug  
and pumped 100 sk 50-50 poz 6% gel, -displaced with 14 bbl water -capped 5 1/2 csg  
with 20 sk 50-50 poz cmt 6% gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Marney  
Well Plugging Supervisor

INVOICED

DATE 8-21-72

INV. NO. 60189-47