

15-135-20515-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1971
CONSERVATION DIVISION
Wichita, Kansas

12-10-1971

Operator's Full Name Champlin Petroleum Company
Complete Address Box 308 Ellinwood, Kansas
Lease Name Bondurant Well No. 1
Location 145° E. of C SE SE Sec. 26 Twp. 18 Rge. (E) (W) 25
County Ness Total Depth 4520'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Strata Drlg.
Address Wichita, Kansas License No.

Operation Completed: Hour 5 A Day 7 Month 12 Year 1971

The above well was plugged as follows:
RTD 4520' 8 5/8 csg set at 355' cwc Cmt. Mat. 50-50 poz W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
DATE 12/10/71
INV. NO. 4807-4

Signed: Leo F. Murray
Well Plugging Supervisor