

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-165-21,344-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Williamson Drilling, Inc. OPERATORS LICENSE NO. 4087

ADDRESS 5501 Navajo, Great Bend, Ks. 67530 PHONE # (316) 793-9229
165' E of

LEASE (FARM) Krug 'A' WELL NO. 1 WELL LOCATION NW NE SW COUNTY Rush

SEC. 29 TWP. 16s RGE. 19 (R) or (W) TOTAL DEPTH 3900' PLUG BACK TO _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 252' CEMENTED WITH 175 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Bottom Plug @ 3827' w/50 sks. Cement thru
drill pipe; Next Plug @ 1357' w/50 sks. Cement thru drill pipe; Next Plug @ 678' w/20 sks.
Cement thru drill pipe; Next Plug @ 282' w/30 sks. Cement thru drill pipe; Top Plug @ 40'
w/10 sks. Cement & 1 sk. Hulls. 10 sks. Cement in Rathole. Well plugged w/230 sks. 60/40
Poz, 6% Gel, 3% CC
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 12-19-85 @ 9:55 A.M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Williamson Drilling, Inc. PHONE # (316) 793-8229

ADDRESS 5501 Navajo, Great Bend, Ks. 67530

PLUGGING CONTRACTOR Williamson Drilling, Inc. LICENSE NO. 4087

ADDRESS 5501 Navajo, Great Bend, Ks. 67530 PHONE # (316) 793-8229

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Terry L. Williams
(Operator or Agent)

DEC 31 1985
12-30-85
CONSERVATION DIVISION

DATE: 12-26-85