

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22535-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 16-18S-11W
1650 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SCHEPMANN Well #: 3
County: BARTON Total Vertical Depth: 3384 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3372		125 SX
SURF	8.625	271		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/09/2012 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY Phone: (620) 793-9090

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/09/2012 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Cut casing at 1505'.
Pulled to 1450'. Pumped 125 sx cement w/200 # hulls.
Pulled casing to 900'. Pumped 75 sx cement w/100 # hulls.
Pulled casing to 630'. Pumped 50 sx cement w/100 # hulls.
Pulled casing to 250'. Circulated cement w/70 sx cement.
Pulled casing. Hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3372	3384		
3084	3258		

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

District: 04

Signed Bruce Rodie
8/15/12 (TECHNICIAN)

CM

JUL 11 2012

Form CP-2/3

RECEIVED
AUG 02 2012
KCC WICHITA