

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20769-00-00
Spot: NWSENE Sec/Twnshp/Rge: 36-15S-13W
3630 feet from S Section Line, 990 feet from E Section Line
Lease Name: SELLENS C Well #: 4
County: RUSSELL Total Vertical Depth: 3338 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3338		100 SX
SURF	8.625	467		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/12/2012 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: GRADY BOLDING Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 564-2240

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls and 10 sx gel.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2012 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450'-840' and 430'.
Ran tubing to 3200'. Pumped 9 sx gel followed w/75 sx cement w/200 # hulls.
Pulled tubing to 1500'. Pumped 65 sx cement w/100 # hulls.
Pulled tubing to 850'. Pumped 65 sx cement w/100 # hulls.
Pulled tubing to 450'. Pumped 50 sx cement. Cement circulated out of casing. Pulled tubing.
Pressured to 200 psi. Shut in.
Tied to surface pipe. Pumped 15 sx cement. Pressured to 200 psi. Shut in.

Perfs:

Remarks: COPELAND ACID AND CEMENTING

Plugged through: ESG TSG

RECEIVED
AUG 02 2012
KCC WICHITA

District: 04

Signed Bruce Rodie
8/15/12 (TECHNICIAN) CM

JUL 19 2012