

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23812-00-00
Spot: SESWNWNE Sec/Twnshp/Rge: 5-15S-15W
1270 feet from N Section Line, 2200 feet from E Section Line
Lease Name: MUDD TRUST Well #: 1-5
County: RUSSELL Total Vertical Depth: 3500 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	739		325 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/26/2012 12:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: RANDY Company: VAL ENERGY, INC. Phone: (620) 282-1496

Proposed Plugging Method: Ordered 205 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 07/26/2012 8:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st plug @3383 w/25 sx
2nd plug @976 w/25 sx
3rd plug @425 w/100 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

RECEIVED
AUG 02 2012
KCC WICHITA

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

✓ 8/15/12