

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-00196-00-00
Spot: SE Sec/Twnshp/Rge: 16-23S-38W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: BEIDERWELL Well #: 2
County: KEARNY Total Vertical Depth: 2689 feet

Operator License No.: 32864
Op Name: XTO ENERGY INC.
Address: 210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2560		
PROD	5.5	2687	0	WITH 200 SX CMT
SURF	8.625	304		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/10/2012 11:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: ROYCE Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: LOAD HOLE W/ 9 PPG MUD. TIH TO 2650' & PUMP 100' CMT PLUG FROM 2550' - 2650'. POOH TO 2080' & PUMP 100' CMT PLUG FROM 1980' - 2080'. (ANHYDRITE @ 2030'). POOH TO 1050' & PUMP 100' CMT PLUG FROM 950' - 1050' (BASE OF TREATABLE WATER @ 1000'). POOH TO 354' & PUMP A 350' CMT PLUG FROM 4' - 354' (SURF CSG SHOE @ 304'). WELD ON ID PLATE. RESTORE LOCATION.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2012 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2560'. PLUG AT 2560' TO 1980' WITH 60 SX CMT. 7/11/12: PERFORATE AT 1050'. RUN TBG & PACKER TO 750'. INJECTION RATE 2 1/2 BPM @ 650#. MIX & PUMP 75 SX CMT WITH 1 SX HULLS IN LAST 25 SX CMT WITH 55 SX CMT OUT OF PERFS. WELL SHUT OFF TO 1400# LEAVING 20 SX CMT INSIDE CASING. NO BLOW OR CIRCULATION UP ANNULUS. TOOH W/TBG. TEST CASING TO 500#. HOLDING. PERFORATE AT 360'. INJECTION RATE 2 BPM @ 50 PSI WITH FULL CIRCULATION. RAN OUT OF CMT. 7/12/12: CIRCULATE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT USING 115 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2660	2670		
2634			
2610	2626		

RECEIVED
AUG 03 2012
KCC WICHITA

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
8/15/12
(TECHNICIAN)

RECEIVED

JUL 23 2012

KCC DODGE CITY

AND