

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-23936-00-00  
Spot: E2SESW Sec/Twnshp/Rge: 22-25S-5E  
660 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: MILLS A Well #: 40  
County: BUTLER Total Vertical Depth: 2520 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1580		
CIBP		2340		
CIBP		2450		
CIBP		2512		
PROD	5.5	2519		125 SX
SURF	8.625	269		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/20/2012 8:00 AM  
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.  
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE  
Date/Time Plugging Completed: 07/20/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 630', CONSOLIDATED WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL, 2% CC 50# HULLS TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING. SWEDGED INTO 5-1/2" CASING & SQUEEZED CEMENT ON BACKSIDE, SHUT IN PRESSURE @ 700#. PLUG DOWN 5:00 PM., 7-20-2012. CONSOLIDATED OIL WELL SERVICES TICKET #34796. BRIDGE PLUGS SET @ 2512', 2450', 2340', & 1580'.

Perfs:

Top	Bot	Thru	Comments
2515	2519	CSG	
2507	2510	CSG	
2384	2388	CSG	
2227	2247	CSG	


RECEIVED  
AUG 03 2012  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

8/15/12

✓ SK