

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-00341-00-01
Spot: NENWSW Sec/Twnshp/Rge: 14-21S-10W
2310 feet from S Section Line, 4290 feet from E Section Line
Lease Name: FAIR DOWWO Well #: 1-14
County: RICE Total Vertical Depth: 3150 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3112		
PROD	4.5	3117		150 SX
SURF	8.625	252		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/01/2012 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: FG HOLL CO LLC Phone: (620) 564-3831

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: PATRICK SHIELDS Witness Type: PARTIAL
Date/Time Plugging Completed: 08/01/2012 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. RUN TUBING TO 3100' AND PUMP 25 SX'S CEMENT WITH 150#'S COTTON HULLS. LET SET--TAGGED AT 2700'. PERFORATE AT 1150', 750', AND 300'. RUN TUBING TO 1150' AND PUMP 35 SX'S CEMENT, PULL TUBING TO 750' AND PUMP 35 SX'S CEMENT, PULL TUBING TO 300' CIRCULATE 165 SX'S CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3049	3051	CSG	LANSING KANSAS

RECEIVED
AUG 07 2012

KCC WICHITA

Remarks: 60-40 4% GEL. PIONEER WIRELINE TICKET #37438. QUALITY WELL CEMENT #5099. TA THAT HAD BEEN DENIED DUE TO HIGH FLUID.

Plugged through: TBG

District: 02

Signed Virgil Clothier
8/15/12 (TECHNICIAN)