

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20276-00-00  
Spot: SWNESWSW Sec/Twnshp/Rge: 36-32S-31W  
676 feet from S Section Line, 4530 feet from E Section Line  
Lease Name: GANOD Well #: 1  
County: SEWARD Total Vertical Depth: 6050 feet

Operator License No.: 6230  
Op Name: FIRST NATIONAL OIL, INC.  
Address: 1755 S BROADWAY ST STE 6  
OVIEDO, FL 32765

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2600		WITH 2 SX CMT
CIBP		2730		
PROD	5.5	6048	2194	WITH 320 SX CMT
SURF	8.625	1536		WITH 650 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/31/2012 3:00 PM  
Plug Co. License No.: 7840 Plug Co. Name: BORDERLINE, INC.  
Proposal Rcvd. from: MIKE BRADY Company: BORDERLINE Phone: (620) 629-5660

Proposed Plugging Method: CIBP @ 2600' WITH 2 SX CMT. PLUG AT 1580' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE  
Date/Time Plugging Completed: 07/31/2012 5:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 2600' WITH 2 SX CMT. 1ST PLUG AT 1575' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 606' WITH 40 SX CMT. 3RD PLUG AT 61' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2634	2643		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

RECEIVED

AUG - 1 2012

KCC DODGE CITY

RECEIVED

AUG 08 2012

KCC WICHITA

(TECHNICIAN)

Form CP-2/3

1907