

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-24049-00-00  
Spot: SENEWNE Sec/Twnshp/Rge: 3-10S-16W  
1672 feet from N Section Line, 1474 feet from E Section Line  
Lease Name: BECKER Well #: D-1  
County: ROOKS Total Vertical Depth: 3480 feet

Operator License No.: 6627  
Op Name: PROSPECT OIL & GAS CORP  
Address: PO BOX 837  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218		150 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/29/2012 12:00 AM  
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC.  
Proposal Rcvd. from: DAN Company: SHIELDS OIL PRODUCERS INC. Phone: (785) 735-4503

Proposed Plugging Method: Ordered 245 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: NONE  
Date/Time Plugging Completed: 06/29/2012 8:45 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

1st plug @3390 w/25 sx  
2nd plug @1125 w/25 sx  
3rd plug @650 w/100 sx  
4th plug @270 w/40 sx  
5th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Remarks: QUALITY

Plugged through: DP

District: 04

Signed Darrel Dipman  
RECEIVED (TECHNICIAN)  
AUG 08 2012 8/16/12  
KCC WICHITA

CM

JUL 27 2012