

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-023-20293-00-00  
Spot: NENWNWSW Sec/Twnshp/Rge: 16-2S-41W  
2312 feet from S Section Line, 4848 feet from E Section Line  
Lease Name: OCHSNER Well #: 16-12-1  
County: CHEYENNE Total Vertical Depth: 3550 feet

Operator License No.: 33325  
Op Name: PDC ENERGY, INC.  
Address: 1775 SHERMAN ST, STE 3000  
DENVER, CO 80203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3543		75 SX
SURF	7	257		35 SX

Well Type: SWD UIC Docket No: D26211.0 Date/Time to Plug: 05/17/2012 8:00 AM  
Plug Co. License No.: 8273 Plug Co. Name: EXCELL SERVICES, LLC  
Proposal Rcvd. from: CHAD SAILORS Company: PDC Phone: (970) 630-2815

Proposed Plugging Method: Ordered 315 sx common cement. Plug through tubing.  
7" surface casing set @ 257' w/35 sx cement. 4 1/2" production casing set @ 3543 w/75 sx cement.  
TD 3550', PBT 3489'. Perforations: 3392'-3462'. Cement squeezes from 1710'-1712' and 2738'-2740' w/75 sx cement.  
Production casing has holes @ 1709'-1711'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/17/2012 12:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Set CIBP @ 3330' to shut off H2 gas so well could be serviced.  
Ran tubing to 3330'. Connected to tubing and pumped 125 sx common cement.  
Pulled tubing to 1760'. Connected to tubing and pumped 90 sx common cement. Cement to surface.  
Pulled tubing to surface. Checked cement top. Ran 1 joint of tubing into well. Connected to tubing and pumped 10 sx cement. Casing full. Connected to 7" surface casing. Pumped 10 sx cement. Casing ruptured.

Perfs:

Top	Bot	Thru	Comments
3392	3462		

Remarks: PLUG COMPLETE. EXCELL SERVICES LLC TICKET # 4537,4538 AND 4539. WRAY REDIMIX.

Plugged through: TBG

District: 04

Signed

*Darrel Dipman*

(TECHNICIAN)

RECEIVED

AUG 08 2012

KCC WICHITA

Form CP-2/3