

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-22009-00-00  
Spot: NENESWSW Sec/Twnshp/Rge: 30-14S-28W  
1130 feet from S Section Line, 1300 feet from W Section Line  
Lease Name: EVANS A Well #: 1  
County: GOVE Total Vertical Depth: 4358 feet

Operator License No.: 33922  
Op Name: MUSTANG ENERGY CORPORATION  
Address: PO BOX 1121  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		150 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/27/2012 12:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL WitnessType: NONE  
Date/Time Plugging Completed: 07/27/2012 3:45 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

1st plug @2010 w/25 sx  
2nd plug @1050 w/100 sx  
3rd plug @270 w/40 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Remarks: CONSOLIDATED

Plugged through: DP

District: 04

Signed Ray A Dinkel (TECHNICIAN) CM

AUG 06 2012

RECEIVED  
AUG 08 2012

KCC WICHITA