

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20577-00-01
Spot: NWSWNESE Sec/Twnshp/Rge: 14-3S-27W
1669 feet from S Section Line, 1117 feet from E Section Line
Lease Name: ELVIN Well #: 4
County: DECATUR Total Vertical Depth: 3850 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3845		125 SX
SURF	8.625	226		225 SX

Well Type: EOR UIC Docket No: E28097.1 Date/Time to Plug: 07/18/2012 12:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 269-7290

Proposed Plugging Method: 8 5/8" surface casing set @ 226' w/225 sx cement. 4 1/2" production casing set @ 3845' w/125 sx cement. 4 1/2" production casing perforated @ 1500' w/150 sx cement, 950' w/150 sx cement and 725' w/125 sx cement. Cement was circulated to surface. Total Depth 3850', PBD 3804'. Perforations 3522'-3526', 3577'-3580', 3594'-3598', 3615'-3617', 3627'-3631' and 3675'-3678'. Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls. Plugged through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/18/2012 2:45 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing @ 2230'. Ran tubing to 3510'. Pumped 80 sx cement w/300 # hulls. Pulled tubing to 2423'. Pumped 80 sx cement w/200 # hulls. Pulled tubing to 1163'. Pumped 110 sx cement w/75 # hulls. Cement to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 20 sx cement. Casing full. Connected to 8 5/8" surface casing. Pumped 5 sx cement. Maximum pressure 250 psi. Plug complete.

Perfs:

Top	Bot	Thru	Comments
3675	3678		
3663	3664		
3627	3631		
3615	3617		
3594	3598		
3577	3580		
3522	3526		

Remarks: SWIFT SERVICES CEMENT TICKET # 21,813

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

RECEIVED

CM

AUG 08 2012

Form CP-2/3

JUL 19 2012

KCC WICHITA