

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20198-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 28-14S-14W
4281 feet from S Section Line, 1062 feet from E Section Line
Lease Name: OLSON A J - B Well #: 5
County: RUSSELL Total Vertical Depth: 3300 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 380 SOUTHPOINTE BLVD #130
CANONSBURG, PA 15917

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3200		
PROD	5.5	3300		350 SX
SURF	8.625	825		500 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/31/2012 8:45 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: KIM HOFFMAN Company: EMPIRE ENERGY Phone: (620) 282-7893

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/20 # hulls and 7 sx gel Perforations: 400', 800', 1400'. CIBP plug set @ 3200'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/31/2012 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2975'. Pumped 7 sx gel followed w/75 sx cement w/100 # hulls.
Pulled tubing to 1408'. Pumped 115 sx cement w/100 # hulls.
Cement circulated out back side, shut valve.
Pumped 135 sx cement.
Cement circulated out the braden head.
POOH. Topped off w/25 sx cement.

Perfs:

Top	Bot	Thru	Comments
3219	3331		
3066	3078		

Remarks: QUALITY CEMENTING TICKET # 764

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

AUG 01 2012

RECEIVED

AUG 08 2012

KCC WICHITA