

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26334-00-00
Spot: E2NENENW Sec/Twnshp/Rge: 24-13S-20W
330 feet from N Section Line, 2400 feet from W Section Line
Lease Name: JOHNSTON Well #: 1
County: ELLIS Total Vertical Depth: 3849 feet

Operator License No.: 33786
Op Name: DOUBLE D'S LLC
Address: 133 E 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/28/2012 12:00 AM
Plug Co. License No.: 5655 Plug Co. Name: SHIELDS DRILLING CO., INC.
Proposal Rcvd. from: TOM Company: SHIELDS DRILLING CO., INC. Phone: (785) 735-4503

Proposed Plugging Method: Ordered 245 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE
Date/Time Plugging Completed: 07/28/2012 11:00 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st plug @3770 w/25 sx
2nd plug @1490 w/25 sx
3rd plug @720 w/100 sx
4th plug @260 w/40 sx
5th plug @ 40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

District: 04

Signed Ed Schumacher

(TECHNICIAN)

CM

RECEIVED
AUG 08 2012

8/15/12

Form CP-2/3

KCC WICHITA