

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23841-00-00
Spot: NESWNE Sec/Twnshp/Rge: 8-10S-24W
1650 feet from N Section Line, 1650 feet from E Section Line
Lease Name: HERMAN-DREILING UNIT "A" Well #: 1-8
County: GRAHAM Total Vertical Depth: 4050 feet

Operator License No.: 34579
Op Name: COBALT ENERGY LLC
Address: 115 S. BELMONT #12 PO BOX 8037
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		165 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/28/2012 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MR. FARR Company: MURFIN DRILLING CO., INC. Phone: (785) 475-7203

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL WitnessType: NONE
Date/Time Plugging Completed: 07/28/2012 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

1st plug @2115 w/25 sx
2nd plug @1230 w/100 sx
3rd plug @270 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: CONSOLIDATED

Plugged through: DP

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

cm

RECEIVED

8/15/12

AUG 08 2012

Form CP-2/3

KCC WICHITA

AUG 8 2012