

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21754-00-00
Spot: S2S2S2 Sec/Twnshp/Rge: 7-24S-23W
400 feet from S Section Line, 2600 feet from W Section Line
Lease Name: CITY OF JETMORE Well #: 1
County: HODGEMAN Total Vertical Depth: 4835 feet

Operator License No.: 31093
Op Name: BECKER OIL CORPORATION
Address: PO BOX 1150
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	359		WITH 225 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/31/2012 7:00 AM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Rcvd. from: MIKE KERNS Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: 1ST PLUG AT 1640' WITH 50 SX CMT. 2ND PLUG AT 810' WITH 60 SX CMT. 3RD PLUG AT 360' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 07/31/2012 9:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 1640' WITH 50 SX CMT. 2ND PLUG AT 810' WITH 60 SX CMT. 3RD PLUG AT 360' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
JUL 31 2012
KCC WICHITA
MP

Signed

Michael Maier
RECEIVED (TECHNICIAN)
AUG 08 2012 *8/15/12*
KCC WICHITA

MAIE