

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21505-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 22-19S-29W  
981 feet from S Section Line, 1617 feet from E Section Line  
Lease Name: HANSEN Well #: 1  
County: LANE Total Vertical Depth: 4702 feet

Operator License No.: 34515  
Op Name: 6G TWISTER, INC.  
Address: PO BOX 1686  
GILLETTE, WY 82717

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4344		
DVT		2127		WITH 223 SX CMT
PROD	4.5	4510	0	
SURF	8.625	304		WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/31/2012 9:00 AM  
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC  
Proposal Rcvd. from: LEE GREENE Company: GREENE ENTERPRISE OF KANSAS Phone: (307) 682-7380

Proposed Plugging Method: CIBP OR 30 SX CMT & 10 SX GEL AT 4050'. RUN TBG TO 2130' & CIRCULATE CMT. PRESSURE TEST 8 5/8" X 4 1/2" WITH 50 SX CMT TO 500 PSIG.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/31/2012 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4050' & PUMP 10 SX GEL & 30 SX CMT. PULL TBG TO 2130' & PUMP 200 SX CMT. CMT CIRCULATED. PULL TBG & TOP OFF WITH 55 SX CMT. TIE ONTO BACKSIDE & PUMP 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4420	4422		
4410	4416		
4349	4351		
4332	4334		
4331	4333		
4302	4305		
4110	4114		

Remarks: USED 60/40 POZMIX 4% GEL BY SCHIPPERS OF HOXIE.

Plugged through: TBG

District: 01

Signed: Michael Maier  
RECEIVED (TECHNICIAN)  
8/15/12

AUG 08 2012

KCC WICHITA

RECEIVED  
JUL 31 2012  
KCC DODGE CITY

Form CP-2/3

BM7