

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-19002-00-02
Spot: W2SW Sec/Twnshp/Rge: 14-20S-33W
1320 feet from S Section Line, 4620 feet from E Section Line
Lease Name: MARK B Well #: 2
County: SCOTT Total Vertical Depth: 4690 feet

Operator License No.: 3045
Op Name: LANG, KENNETH R.
Address: 301 W BELLEVUE
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	4.5	1516	0	WITH 815 SX CMT
PROD	7	4687	0	WITH 350 SX CMT
SURF	10.75	235		

Well Type: SWD UIC Docket No: D20701.0 Date/Time to Plug: 07/26/2012 9:00 AM
Plug Co. License No.: 8438 Plug Co. Name: POST & MASTIN WELL SERVICE, INC.
Proposal Rcvd. from: KENNETH LANG Company: KENNETH LANG Phone: (620) 275-4573

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 30 SX CMT. PULL TBG TO 900' & CIRCULATE TO SURFACE. TIE ONTO BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/27/2012 12:05 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 1421' & PUMP 30 SX CMT. PULLED TBG TO 904' & PUMPED 100# CMT & 400# HULLS. DID NOT CIRCULATE. PULLED TO 500' & WAITED 45 MINUTES. PUMPED 8 BBL WATER. DID NOT GET ANY BLOW. SDON. 7/27/12: TIH W/TBG & TAG TOC IN 4 1/2" LINER AT 1162'. BREAK CIRCULATION WITH 1/2 BBL WATER. FULL RETURNS. PULL TBG TO 1130' & PUMP 50 SX CMT WITH 100# HULLS. FULL RETURNS. PULL TBG TO 325' & CIRCULATE CMT TO SURFACE WITH 25 SX CMT. FULL RETURNS & STAYED FULL. TOOH W/TBG & TOP OFF 4 1/2" WITH 5 SX CMT. HOOK UP TO 4 1/2" X 7" ANNULUS & FILL TO SURFACE WITH 15 SX CMT. 7" X 10 3/4" IS ALREADY FULL OF CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
1642	1654		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed Michael Maier (TECHNICIAN)
8/15/12
RECEIVED JUL 31 2012 KCC DODGE CITY
RECEIVED AUG 08 2012 KCC WICHITA
cc to UIC 8/09/12 Form CP-2/3
RMY