

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20995-00-00
Spot: NWNESE Sec/Twnshp/Rge: 34-12S-32W
2548 feet from S Section Line, 352 feet from E Section Line
Lease Name: DALE Well #: 1-34
County: LOGAN Total Vertical Depth: 4750 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4740		175 SX
SURF	8.625	216		165 SX
TI	2.875	4693		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/31/2012 2:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN JOHNSON-GRAND M Company: _____ Phone: (620) 617-3357

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix 4% gel cement w/400 # hulls and 14 sx gel.
Perfs: 4563' to 4567'
DV tool @ 2520'.
Ran out of cement. Had to go get 75 more sx cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/31/2012 5:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing. Pumped 50 sx cement w/100 # hulls followed with 14 sx gel. Pumped 255 sx cement w/200 # hulls. Not full. Stopped pumping cement and let set. Tied on to back side. Pumped 15 sx cement. Shut in pressure @ 400 psi. Ran out of cement. Had to get more cement to finish topping off casing. Topped off casing w/25 sx cement. Hole Standing full.

Perfs:

Top	Bot	Thru	Comments
4563	4567		

Remarks: SWIFT SERVICES TICKET # 21731

Plugged through: CSG

District: 04

Signed

Marvin Mills
RECEIVED (TECHNICIAN)

CM

AUG 08 2012

8/18/12

Form CP-2/3

KCC WICHITA