

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21930-00-00
Spot: SESESE Sec/Twnshp/Rge: 27-13S-20W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: GIEBLER Well #: 6
County: ELLIS Total Vertical Depth: 3847 feet

Operator License No.: 33636
Op Name: TRIUNITED INVESTORS, LLC
Address: 18598 TWIN CREEKS RD
MONTE SERENO, CA 95030

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3843		125 SX
SURF	8.625	176		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/02/2012 9:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Revd. from: JOHN FOSE Company: TRIUNITED INVESTORS LLC Phone: (785) 623-0002

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Casing leaks
PBTD- 3835'
Perfs: 3796'-3800', 3844'-3847'

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/02/2012 2:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf tech perfed @ 2050', 1539', 838'.
Professional Pulling Services ran in hole with tubing to 3613'. Quality Well Cementing rigged to tubing, mixed and pumped 160 sx cement w/300 # hulls.
Pulled tubing to 1997' Quality rigged to tubing, mixed and pumped 210 sx cement w/200 # hulls to circulate cement to pit area.
Pulled tubing. Topped off 5 1/2" casing w/65 sx. Hole standing full.
Rigged to 8 5/8" casing. Pumped 1 sx cement. Instant pressure on back side.

Perfs:

Top	Bot	Thru	Comments
3844	3847		
3796	3800		

Remarks: QUALITY WELL CEMENTING TICKET # 5614

Plugged through: TBG

District: 04

Signed [Signature]
RECEIVED (TECHNICIAN)
AUG 08 2012 8/15/12

AUG 02 2012

KCC WICHITA