

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21074-00-00
Spot: N2SENV Sec/Twnshp/Rge: 30-7S-17W
3630 feet from S Section Line, 3300 feet from E Section Line
Lease Name: KU 'A' Well #: 1
County: ROOKS Total Vertical Depth: 3288 feet

Operator License No.: 32278

Op Name: TENGASCO, INC.

Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3283		
PROD	4.5	3283		75 SX
SURF	8.625	1218		550 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/19/2012 8:30 AM

Plug Co. License No.: 32332

Plug Co. Name: FISCHER WELL SERVICE, INC.

Proposal Rcvd. from: GARY WAGNER

Company: TENGASCO INC.

Phone: (785) 625-6374

Proposed Method: Ordered 475 sx 60/40 pozmix4% gel cement w/500 # hulls.
Production perforation: 3064'-3067', 3100'-3102', 3128'-3132', 3253'-3256' and 3267'-3270'.
Perforated @ 1195'

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/19/2012 11:30 AM

KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2800'. Pumped 100 sx cement w/200 # hulls.
Pulled tubing to 1764'. Pumped 100 sx cement to circulate to surface. Closed off backside.
Pumped 65 sx cement. Circulated out 8 5/8"x4 1/2" annulus. Lost circulation and pressured to 1000#s.
Pulled all tubing. Hooked to 4 1/2" casing. Pumped 20 sx cement to top off 4 1/2" casing and circulate 8 5/8" x 4 1/2" annulus to surface. Shut in pressure 300 psi.

Perfs:

Top	Bot	Thru	Comments
3267	3270		
3253	3256		
3128	3132		
3100	3102		
3064	3067		

Remarks: ALLIED CEMENTING TICKET # 56457

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

RECEIVED

AUG 08 2012

Form CP-2/3

KCC WICHITA