

GIINTHER WELL NO. 1

CENTER SW-NW SE
SEC. 17-11S-19W
ELLIS COUNTY, KANSAS

CONTRACTOR: THE R. W. RINE DRILLING COMPANY
STARTED: JUNE 3, 1952

FINISHED: JUNE 14, 1952


	LOG		
SAND AND SHALE	0	275	C-3/8" Cas. @ 260' w/200 sx. w/2" C.C.
SAND AND SHALE	275	500	Syfo @ 500' - 1°
SAND, SHALE AND SHELLS	500	770	
SAND	770	1025	
SHALE AND RED BED	1025	1300	
SHALE AND SHELLS	1300	1615	Syfo @ 1600' - 1°
SHALE AND SHELLS	1615	1910	
LIME AND SHELLS	1910	2070	Syfo @ 2000' - OK
LIME	2070	2230	
LIME	2230	2485	
LIME AND SHALE	2485	2615	Syfo @ 2600' - OK
LIME AND SHALE	2615	2740	
LIME, SHALE AND SHELLS	2740	2810	
LIME AND SHALE	2810	2925	
LIME AND SHALE	2925	3125	Syfo @ 3000' - 1°
LIME	3125	3170	
LIME AND SHALE	3170	3235	
LIME	3235	3303	
LIME	3303	3425	
LIME	3425	3575	
LIME AND SAND	3575	3630	
CHERT	3630	3655	R.T.O. @ 3655' BOTTOM PLUG @ 240' w/ 20 SK. CEMENT TOP PLUG @ 40' w/ 1/2 SK. HULLS AND 10 SK. CEMENT. HEAVY MUD BETWEEN PLUGS.

I, E. H. SLOYER, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND ACCURATE LOG OF THE GIINTHER WELL NO. 1, LOCATED CENTER SW, NW, SE, SECTION 17-11S-19W, ELLIS COUNTY, KANSAS.

E. H. Sloyer
SECRETARY-TREASURER

SUBSCRIBED TO AND SWORN BEFORE ME THIS 16TH DAY OF JUNE, 1952.

Leana U Pederson
NOTARY PUBLIC



MY COMMISSION EXPIRES APRIL 20, 1953.

RECEIVED
STATE COMMISSION - CONSERVATION
JUN 25 1952
CONSERVATION DIVISION
Wichita, Kansas

17-11S-19W
26-3