

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ellis - Kansas County. Sec. 17 Twp. 11 Rge. (E) 19 (W)

Location as "NE/CNW/SW" or footage from lines NE SW NW

Lease Owner MURFIN DRILLING COMPANY

Lease Name Arvel C. Smith Giinther #2, now Murfin Drilling Co. Giinther "B" SW 1/4

Office Address 617 Union Center - Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) SWD Well

Date well completed 7-10 19 63

Application for plugging filed 7-28 19 67

Application for plugging approved 7-31 19 67


Plugging commenced 7-31 19 67

Plugging completed 7-31-1967

Reason for abandonment of well or producing formation discontinued use of well

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 3608 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped 100 sacks common cement down casing 1200# maximum pressure 500# Standing Pressure shut-in let cement set.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor MURFIN DRILLING COMPANY
Address 617 UNION CENTER - WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. R. Murfin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) MURFIN DRILLING COMPANY

W. R. Murfin (Address)

Subscribed and sworn to before me this 30th day of August, 1967



Adela Mizener Notary Public

My commission expires November 5, 1970

DRILLERS LOG

Ginther #2

CASING RECORD:	COMPANY:	Arvel C. Smith	DESCRIPTION:
8 5/8" @ 250 w/150 sx cement	CONTRACTOR:	Red Tiger Drilling Co.	NE & W NW 17-11S-19W
4 1/2" @ 900 w/300 sx cement	COMMENCED:	May 26, 1963	Ellis County Kansas
TOTAL DEPTH:	COMPLETED:	June 5, 1963	ELEVATION:
3608			2007 DF 2010 RB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Blue Shale	0	210	
Cement	210	250	
Shale	250	600	
Shale & Shells	600	800	
Sand	800	1080	
Shale	1080	1320	
Shale & Shells	1320	1368	
Anhydrite	1368	1406	
Shale & Shells	1406	1735	
Shale	1735	1890	
Shale & Lime	1890	3070	
Lime	3070	3598	
Arbuckle	3598	3608	

RECEIVED
STATE CORPORATION COMMISSION

DEC 4 1963

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle
George A. Angle

Subscribed and sworn to before me this 6th day of June, 1963.

Doraine V. Head
Notary Public

My Commission Expires:

11-17-66

