

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County, Sec. 14 Twp. 11S Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SW NW

Lease Owner Don E. Pratt

Lease Name H. Vine Well No. 2

Office Address Box 656 - Hays, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed January 30 1952

Application for plugging filed March 12 1955

Application for plugging approved March 15 1955

Plugging commenced March 15 1955

Plugging completed March 18 1955

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3524 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1309'	None
				5-9/16"	3522'	2579'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran 5 sacks of cement at 3524'. Pumped in 20 sacks of jell mud and 75 sacks of cement through surface casing. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF _____, COUNTY OF _____, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Box 656 Hays, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26 day of March 1955

[Signature] Notary Public.

My commission expires October 1, 1955

PLUGGING
FILE SEC 14 T 11 R 19W
BOOK PAGE 103 LINE 45

RECEIVED
MAR 28 1955
INSERV. 03-28-55

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15051-19466-0000

Company- DON PRATT OIL CO.
Farm- H. Vine No. 2

SEC. 14 T. 11 R.19W
SE SW NW

Total Depth. 3524
Comm. 11-13-51 Comp. 1-30-52
Shot or Treated.
Contractor. Overland Drlg.
Issued. 7-19-52

County Ellis
KANSAS



CASING:
8 5/8" 1309' cem. w/550 sx.

Elevation. 1981 D.F.

Production. 32 bbls. / 6% wtr.

Figures Indicate Bottom of Formations.

surface soil	15
sand, shale	70
shale, shells	182
cement 176-182	
shale, shells	500
sand	580
shale, shells	760
sand	1060
redbed	1110
shale, shells	1300
anhyd.	1347
shale	1438
Total Depth Completed 11-17-51	
11-18-51 Comm.	
surface soil	15
shale, sand	71
clay, shale & shells	365
shale, shells	500
sand	600
shale, shells	680
lime	705
shale, shells	739
sand Dakota	840
sand	940
shale, shells	1050
redbed	1100
shale, shells	1280
shale, sand	1303
anhyd.	1310
cement 1305-10	
anhyd.	1343
redbed, shells, shale	1480
(broke down 11-23-52 until 12-29-52)	
shale red, shells	1825
shale, shells	1865
shale, lime	1930
shale, shells	1965
sand, shale	2100
shale, lime	2350
SLM @ 2148 = 2148	
shale, sand	2495
shale, lime	2555
lime	2615
lime, shale	2918
Arb.	3524
Total Depth	

Tops: Scout	
Heebner	3168
Lansing	3209
Congl.	3450
Simpson	3502
Arbuckle	3521

PLUGGING
PAGE 1
BOOK PAGE LINE

STATE