

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County. Sec. 14 Twp. 11 Rge. 19W (E) (W)

Location as "NE/CNW%SW%" or footage from lines NE NE SE

Lease Owner C-G Drilling Co. & Houston, Chandler & Simpson  
Lease Name Devine Well No. 1011-08.

Office Address 107 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 15 1958

Application for plugging filed December 15 1958

Application for plugging approved December 15 1958

Plugging commenced December 15 1958

Plugging completed December 15 1958

Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3508 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	193.02'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 400'. Set plug. Put in 25 sacks cement. Filled to 180'. Set plug. Put in 1/2 sack hulls and 20 sacks cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack hulls and 10 sacks cement.

RCYD  
12-24-58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.

Address 107 Rule Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway

107 Rule Building (Address)

SUBSCRIBED AND SWORN to before me this 23rd day of December, 1958

Vicky Jacobs Notary Public.



PLUGGING  
FILE SEC 14 T 11 R 19W  
BOOK PAGE 9 LINE 27

CONTRACTOR'S WELL LOG

OPERATOR C-G Drilling Co. & Houston, Chandler & Simpson Oil Co. WELL NAME Devine #1  
 LOCATION NE NE SE SEC. 14-11-19W RIG NO. 2  
 COUNTY Ellis STATE Kansas  
 COMMENCEMENT DATE December 4, 1958 COMPLETION DATE December 15, 1958

LOG OF WELL

Elevation 1932' kelly bushing.  
 All measurements taken from the top of kelly bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	193	Sand-Shale		
193	400	Shale-Sand		
400	485	Shale		
485	585	Sand		
585	1065	Shale-Red Bed		
1065	1273	Shale-Red Bed		
1273	1300	Anhydrite		
1300	1313	Anhydrite		
1313	1510	Shale-Shell		
1510	1660	Shale-Shell		
1660	2400	Shale-Lime		
2400	2505	Shale-Lime	0° - 2500	
2505	2650	Shale-Lime		
2650	2775	Shale-Lime	0° - 2750	
2775	2880	Shale-Lime		
2880	2956	Shale-Lime		
2956	3036	Shale-Lime	0° - 3000	
3036	3098	Lime		
3098	3155	Lime		
3155	3181	Lime		
3181	3232	Lime		DST 3197-3232'
3232	3235	Lime		
3235	3308	Lime	0° - 3250	
3308	3355	Lime		
3355	3412	Lime		
3412	3444	Lime		
3444	3460	Lime		DST 3457-3460'
3460	3465	Lime		
3465	3476	Lime		
3476	3508	Arbuckle		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 193.02' (9 jts.) 8-5/8" OD Surface Casing.

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway  
 G. F. Galloway

SUBSCRIBED AND SWORN TO BEFORE ME THIS 23rd day of December, 1958.

My commission expires: May 20, 1959

Vicky Jacobs  
 Vicky Jacobs, Notary Public

PLUGGING  
 FILE SEC 14 T 11 R 19W  
 BOOK PAGE 9 LINE 27

