


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 14 Twp. 11S Rge. (E) 19 (W)
Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Clinton Oil Co.
Lease Name R. P. Devine 'A' Well No. 3
Office Address P. O. Box 1201, Wichita, Kansas 67201
Character of Well (completed as Oil, Gas or Dry Hole) Oil - then to SWD
Date well completed 10-1 19 51
Application for plugging filed 11-7 19 73
Application for plugging approved 11-8 19 73
Plugging commenced 12-22 19 73
Plugging completed 12-22 19 73
Reason for abandonment of well or producing formation Oil depleted in 1964.
Convert to SWD in 1964.
If a producing well is abandoned, date of last production 4-30- 19 64
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Cedar Hill Depth to top 740 Bottom 995 Total Depth of Well 3483 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1273'	None
				5-1/2"	3482'	2651' - 9-64

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

8-5/8" Csg - 100 sks 50/50 poz w/6% gel & 1 sk hulls - 435' - 0'
25 sks gel & 4 sks hulls - 995-435'

9-29-64 - Pulled 2651' of 5 1/2" csg. Set IBP @ 1255' & dumped 1 1/2 sks cmt on top.
Perf Cedar Hill 740-995.

RECEIVED
STATE CORPORATION COMMISSION

JAN 29 1974 0103-74

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing, Russell, Kansas
Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Ronald E. Rowe (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Ronald E. Rowe

P. O. Box 1201, Wichita, Kansas 67201
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of Jan., 1974

Robert L. Rathbun
Notary Public.

My commission expires

ROBERT L. RATHBUN
State Notary Public
Sedgwick County, Kansas
Comm. Expires Aug. 21, 1977

Wichita
Dunson
e


R.P.

WELL LOG ON DEVINE A-3

Spudding date: August 25, 1951
Date casing set: September 9, 1951
Date rotary completed: September 9, 1951
Date cable completed:

Location:
Sec. 14, T 11S, R 19W
Ellis County, Kansas

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>	<u>REMARKS</u>
0	134	Surface	Set 5 jts 13" csg at 131' w/200 sx cement.
134	1265	Shale & Shells	
1265	1305	Anhydrite	
1305	1820	Shale & Shells	
1820	2140	Lime & Shale & Lime	
2140	2220	Lime	
2220	2315	Sandy Lime	
2315	2560	Lime	
2560	3110	Lime & Shale	
3110	3486	Lime	
2486		TOTAL DEPTH	Set 5 1/2" O.D. casing at 3485 R.B.M. w/100 sx bulk cement.



RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1973
CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me this 13th day of September, 19 51.

I certify the above and foregoing to be a true and exact copy of the original driller's log on the DEVINE A-3.

Elaine Stager
Notary Public
My commission expires:
My commission expires Aug. 28, 1955

HERNDON DRILLING COMPANY
By: CJ Moore
Title: