


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Ellis County. Sec. 12 Twp. 11 Rge. 19 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SE SE NE
Lease Owner Graham-Messman-Rinehart Oil Company
Lease Name Gasaway Well No. 1
Office Address 204 North Market, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 15, 1951 19
Application for plugging filed May 31, 19 51
Application for plugging approved May 25, 19 51
Plugging commenced May 16, 1951 19
Plugging completed May 16, 1951 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elden Petty
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	198	None
				5 1/2	3592	2 3950

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Baker Plug @ 3460
Chat to 3360' 5 sacks
Cement - 30 sacks aquagel
Plug @ 225' 75 sacks
Cement - dirt to surface



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Graham-Messman-Rinehart Oil Company
Address 204 North Market, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland
204 North Market, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of June, 19 51
Oliver Carter
Notary Public.



PLUGGING
FILE SEC 12 T 11 R 19
BOOK PAGE 84 LINE 83

GASAWAY WELL NO. 1

Location: SE/4 SE/4 NE/4 Sec.12-11S-19W
Ellie County, Kansas

Date Spudded: 4-24-51

Operator: Graham-Messman-Rinehart Oil Co.

Date Rotary Completion: 5-5-51

Contractor: Fred Drilling Co.

Total Depth (rotary) 3592'

Elevation: 1997' IF; 1999' KB

Surface Casing: 9 jts. (198' less thds.) 8-5/8"
cemented w/150 sacks Lone Star
Portland (bulk) cement and 2 sacks
Cal.Chloride.

Oil Strings: 113 jts. (3591.62') 5 1/2" cemented
at 3590' w/100 sacks cement.

T O P S (KB)

Anhydrite	1330 (+ 669)
Topeka	2993 (- 994)
Heebner	3213 (-1214)
Lansing-Kansas City	3257 (-1258)
Conglomerate	3514 (-1515)
Arbuckle	3587 (-1588)
Rotary Total Depth	3592 (-1593)

L O G

(Figures indicate bottom of formation)

Sand and shale	0 to 175
Shale	201
Shale and sand	465
Shale and sand	815
Sand	1005
Shale	1040
Shale	1330
Anhydrite	1338
Anhydrite	1374
Shale	1505
Shale and shells and salt	1885
Shale	2030
Shale and lime	2165
Lime	2290
Lime and shale	2740
Shale	2940
Lime and shale	3286
Lime	3451
Lime and shale	3592
Total Depth (rotary)	3592'

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

PLUGGING

FILE SEC. 12 T. 11 R. 19W
BOOK PAGE 54 LINE 23

FRED DRILLING CO.

By

Robert F. Walters

Subscribed and sworn to before me this
9th day of May 1951.

Margaret Matt
(Notary Public)

My commission expires: June 28, 1952