

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23128-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 30-11S-19W
380 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: ZERFAS Well Number: 5
County: ELLIS Total Vertical Depth: 3781 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 273 225 SXS CMT
Production: Size 5.5 feet: 3774 100 SXS CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/26/2001 10:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MIKE STANTON Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered out 15 yards common Red-Mix.
D.V. at 1555' with 400 sxs.
Squeezed at 3685' - 3687' in October 1987.
Squeezed at 3685' - 3691' in September 1982.
Prod. Perfs 3605' - 3691'.
Fluid Level at 1750'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/26/2001 12:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Casing annulus full of cement.
Rigged up Five Star Cementing and dumped 8 yards Redi-Mix common with sand.
Hole full of cement.

INVOICED
DATE 4-30-01
INL. NO. 2001061736


RECEIVED
STATE CORPORATION COMMISSION
APR 30 2001
CONSERVATION DIVISION
Wichita, Kansas

Remarks: FIVE STAR CEMENTING.

Plugged through:

District: 04

Signed



(TECHNICIAN)

MURFIN DRILLING CO. 30-11-19W
 617 UNION CENTER BLDG. #5 ZERFAS 380' FSL &
 WICHITA, KS 67202 1320' FEL, SE/4
 CONTR MURFIN DRG. CO. CTY ELLIS

GEOL _____ FIELD ZERFAS
 E 2137 KB CM 8/20/82 CARD 10/7/82 IP P 38 BO & 161 BWPD
 2132 GL ISSUED ARB 3685-3691
 API 15-051-23,128

+	+
+	+
+	+

LOG	Tops	Depth/Datum
ANH	1489 +	648
B ANH	1527 +	610
TOP	3121-	984
HEEB	3342-	1205
TOR	3359-	1222
LANS	3381-	1244
BKC	3605-	1468
ARB	3680-	1543
PBTD	3722-	1585
TD	3781-	1644

8 5/8 " 272:225SX, 5 1/2. " 3774:600SX
 DST (1) 3376-3430 (TOR, LKC) / 30-60-60-60, REC 1848' SW,
 SIP 1106-1106#, FP 98-415 / 437-854#, HP 1793-1771#
 DST (2) 3450-65 (LKC) / 30-60-60-60, REC 1461' SW, SL SCUM
 OIL, SIP 1148-1148#, FP 220-308 / 363-680#, HP 1853-1831#
 DST (3) 3647-3698 (PENN, ARB) / 30-45-60-90, REC 2892' GO,
 SIP 1151-1151#, FP 546-711 / 833-1118#, HP 1902-1880#
 MICT - CO, PF (ARB) 3685-3691, TSTD GSO, POP, P 38 BO &
 161 BWPD, 9.11.82

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS