

4 060182

4-4

234 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

184 API NUMBER 15- 051-24,722 00-00
NW of N2 S2 SW, SEC. 30, T 11 S, R 19 WEX

990 feet from S section line
4080 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30606

Lease Name Albert Well # 1-30

Operator: Murfin Drilling Company Inc.

County Ellis 122.36

Name & Address 250 N. Water Suite #300

Well Total Depth 3765 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXXX

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pullers License Number 6050

Address Box 347 Chase, KS 67524

Company to plug at: Hour: 9:00AM Day: 4 Month: April Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pullers (phone)

were: Order 300 sxs. cement with hulls

RECEIVED
STATE CORPORATION COMMISSION

Plug coming out of hole with casing.

APR 12 1991

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Marion Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXXXX Part None

Operations Completed: Hour: 4:15PM Day: 4 Month: April Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8" to 263', 5 1/2" to 3764'. Sanded back to 2565' and spotted 5 sxs. cement. Shot one time at 2500' and pulled casing to 1335' and stuck casing in hole. Pmp. 50 sxs. 60/40pos 8%gel Shot casing at 1127' and 729' before working loose. pmp. 180sxcement with circ to surface. Pulled casing and filled to surface with sement 70 sxs.

Remarks: Allied Cementing

INVOICED

(If additional description is necessary, use BACK of this form.)

I (did XXXXXXXX observe this plugging.

DATE 4-23-91

Signed Herb Deines
(TECHNICIAN)

INV. NO. 31640

Herb Deines