

6 070835

4-27 15-051-19467-0000 241

API NUMBER 15- 1962

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NL NE, SEC. 16, T 11 S, R 19 W/E

4950 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT
5245

Operator License # _____

Lease Name Gustus Well # 6

Operator: Okmar Oil Co.

County Ellis 115.08

Name & Address 970 Fourth Financial Center

Well Total Depth 3541 feet

Wichita, Ks. 67202

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 168

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan and Co. Tools License Number _____

Address Box 69 Hays, Ks.

Company to plug at: Hour: 2:00 PM Day: 27 Month: April Year: 19 90

Plugging proposal received from George Jorgenson

(company name) Okmar Oil Co. (phone) _____

were: 8 5/8" - 168' s.p. cwc w/125 sks cement. 5 1/2" casing set at 3541' w/200 sks cement.

Stage collar at 1320' cwc w/390 sks cement. CIBP at 3500'. Proposal - perforate at 1775' and 390'. Order 300 sks 65/35 poz 6% gel. Run 2 3/8" tubing to a min. of 1750'. O.K. by Don Butcher. Circulate cement in 5 1/2" casing and then squeeze with cement pressure annulus with cement shut in under pressure.

Plugging Proposal Received by M. J. S. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 7:00 PM Day: 27 Month: April Year: 19 90

ACTUAL PLUGGING REPORT Okmar ordered 300 sks 65/35 poz 6% gel per 5 1/2" casing at 1775',

1. Ran 2 3/8" tubing at 1750'. Spotted 300 sks cement. 2. Sq annulus with 5 sks cement.
- Max pressure 500 psig. Shut in 300 psig. 3. Returned for another 300 sks 65/3 5 poz 6% gel
- 2% cc and hulls. 4. 2 3/8" tubing at 1280' w/160 sks cement. Cement circ out of 5 1/2"
- casing. 5. Squeezed 5 1/2" casing w/140 sks cement. Max pressure 350 psig. Shut in at 100 psig.

Remarks: Cemented by B. J. Titan
(If additional description is necessary, use BACK of this form.)

INVOICED
(If desired, observe this plugging.)

MAY 23 1990
Wichita, Kansas
R. S.

DATE 5-9-90
INV. NO. 28080

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt