

2-26  
4-060297

15-05105083-0000

19  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 4-29-55

SE SE NE /4 SEC. 16, 11 S, 19 W  
2310 feet from S section line  
330 feet from E section line

Operator license# 5363

Lease Gustus well # 2

Operator: Berexco, Inc.

County Ellis

113.81

Address: P.O. Box 723  
Hays, Kansas 67601

Well total depth 3502 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 1280 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License# -

Address: \_\_\_\_\_

Company to plug at: Hour: 3:00P.M. Day: 26 Month: February Year: 92

Plugging proposal received from: George Jorgensen

Company: Berexco, Inc. Phone: \_\_\_\_\_

Were: Order 265 sxs. 65/35 posmix - 8% gel. and hulls.  
Plug through tubing.  
Junk in hole below 1290'.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 13 1992

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

CONSERVATION DIVISION  
Wichita Kan

Completed: Hour: 5:15P.M., Day: 26, Month: February, Year: 1992

Actual plugging report: 8 5/8" to 1280'. 5 1/2" to 3499'. Tubing stuck below 1290'. Attempt to cut tubing at 1290' but would not pull free. Mixed and pumped 235 sxs of 65/35 posmix, 8% gel. with cement to surface in casing and annulus. Backed off and pulled 42 joints of tubing. Tied onto casing and pumped 30 sxs. cement. Shut in annulus and pressured to 500#. Max. pressure 500#. S.I.P. 500#.

Remarks: B-J Services Cementing.  
Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: 1963 GL

I did  / did not  observe the plugging.

(agent)

INVOICED  
DATE 3-17-92  
INV. NO. 34763