

4 050047

5-29

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-30073-0000
SE SW SW, SEC. 16, T 11 S, R 19 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Operator: Okmar Oil Company
Name & Address Box 723
Hays, Kansas 67601

330 feet from S section line
4290 feet from E section line

Lease Name Simmons Well # 4
County Ellis 113.59

Well Total Depth 3495 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 176

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Services License Number _____
Address _____

Company to plug at: Hour: _____ Day: 29 Month: May Year: 19 90

Plugging proposal received from _____

(company name) Okmar Oil Company (phone) _____

were: Order 350 sks 65/35 poz 8% gel gel w/500 lbs. hulls.
Well record: Surface pipe 8 5/8 set at 1/6" w/150 sks.

5 1/2 casing set at 3492 w/100 sks. Stage collar set at 1265 w/225 sks cement and
87 sks dicel circ. Open hole completion.

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15PM Day: 29 Month: May Year: 19 90

ACTUAL PLUGGING REPORT Ran 2" tubing to 3400'. Pumped 100 sks 65/35
poz 8% gel and 200 lbs. hulls down tubing. PULLED tubing to 1300'. Pumped 130 sks
65/35 poz 8% gel and 200 lbs. hulls down tubing. Cement circ. Pulled all of tubing
tied onto 5 1/2" casing sq 120 sks 65/35 poz 8% gel and 100 lbs hulls at 800# max psi
with 600# psi. Shut in pressure. Backside 0 sks at 500 psi.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 6-12-90
INV. NO. 28419

JUN 11 1990
G.H.S.
CONSERVATION DIVISION
Wichita, Kansas

Signed Marvin S. Miller
(TECHNICIAN)
Marvin Miller