

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00275-00-00
Spot: CNESE Sec/Twnshp/Rge: 16-11S-19W
2310 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: WILES Well Number: 1
County: ELLIS Total Vertical Depth: 3500 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size feet: 8 1/3.75
Surface Casing: Size 8.625 feet: 1270 600 SX CMT
Production: Size 5.5 feet: 3497 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/21/2001 9:00 AM

Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.

Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 415 sxs cement with 500# hulls.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/21/2001 10:30 AM

KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 1270' w/600 sxs cement.
5 1/2" casing at 3497' w/150 sxs cement.
4 1/2" liner to 3466' w/268 sxs cement.
Tied to 5 1/2" casing and pumped 250 sxs cement with 500# hulls.
Max. P.S.I. 900#. S.I.P. 300#.
Tied to 8 5/8" annulus - pumped 15 sxs cement to Max. P.S.I. 300#. S.I.P. 200#.
Total of 265 sxs 60/40 pozmix with 10% gel and 500# hulls.

Remarks: ALLIED CEMENTING COMPANY. BLACKHAWK TANK-WATER.

Plugged through: CSG

District: 04

Signed

Roger S. Moses
(TECHNICIAN)

RECEIVED

INVOICED

Form CP-2/3

JAN 04 2002

DATE

01-07-02

KCC WICHITA

INV NO

2002061208

JAN 02 2002

16-11-19W 33
NE NE SE

OKMAR OIL COMPANY #1 WILES
Contr. GLENN R NYE DRILG COMPANY ELLIS County
E 1959 RB Comm. Comp. 3-27-53 IP 388 BOFD

Tops	Depth	Datum
AW	1266	+1693
FEEB	3145	-1186
LANS	3186	-1227
CONG	3421	-1465
SIMP	3459	-1500
ARB	3496	-1537
TD	3500	-1541

Casing
8" 1270
5" 3497

CO 3500: ACID 500

SOLOMON POOL

+	+	+
+	+	+
+	+	+

Dih 304-604
ANH 1266-1306
Salt 1646-1786

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS