

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02282-00-00
Spot: CNWNWSE Sec/Twnshp/Rge: 16-11S-19W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: WILES Well Number: 3
County: ELLIS Total Vertical Depth: 3503 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: 100 N. BROADWAY, STE. 970
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 173 135 SX CMT
Production: Size 5.5 feet: 3502 250 SX CMT \$113.85
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/27/2001 11:00 AM

Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.

Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 600# hulls.
840' squeezed with 50 sxs. 640' squeezed with 150 sxs. 698' squeezed with 150 sxs.
745' squeezed with 60 sxs. Perf 3165' - 3174'. 960' squeezed - 1308' D.V. - 244 sxs.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/27/2001 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH to 2400' - tied onto tubing and pumped 165 sxs cement and 600# hulls until cement circulated.
Pulled out of hole - tied onto casing and pumped 5 more barrels and 20 sxs cement. Max. P.S.I. 800#. S.I.P. 500#.
Tied onto backside and pumped 6 sxs into backside. S.I.P. 500#.

INVOICED
DATE 4-23-01
INV. NO. 2001061704

RECEIVED
STATE CORPORATION COMMISSION
APR 12 2001
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY - TICKET #6532.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

102

APR 11 2001

5-126 MAP NO. _____ SEC. 16-11S-19W
 STATE Kansas COUNTY Ellis LOC. NW NW SE
 OPER Okmar Oil Co., Wichita, Kansas FT/FR _____ LINE
 WELL #3 FARM Wiles FT/FR _____ LINE
 POOL Sessin, W, Ext. ELEV. _____ GR. 1974 DF 1976 KB
 CONT. Leben Drlg. Co. GEOL. Harold McNeil
 CO. INT. PTD. 3500'
 F.R. 4-14-64 SPUD. 4-10-64 COMP. 5-19-64
 TD 3502 FM. Arb. PBTD. _____

Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
		Arb.	3502	- 03	OH
Casing Record	I.P. Co. P 30 BOPD - Gr. NA				
	8" @173' w/135 Sx.				
	5½" @3502' w/250 Sx.				

Data Inc.

KB Spl Tops:
 Anh 1280 + 696 Lans 3190 -1214
 Hb 3152 -1176 Arb 3501 -1525
 Tor 3172 -1196 RTD 3502 -1526
 DST #1(Tor)3158-88, Op 1 hr, 30' GOP, R 150' HO&SGCM, ISIP 920# /30', IFP 0#, FFP 0#, FSIP 770#/30'.
 DST #2(Lans)3185-3210, Op 1 hr, R 15' M, ISIP 350#/30', IFP 0#