

\* Wrong Well Invoice deleted. Company notified. Correct well is attached this well is not plugged yet.

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-00275-00-00  
Spot: CNESE Sec/Twnshp/Rge: 16-11S-19W  
2310 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: WILES Well Number: 1  
County: ELLIS Total Vertical Depth: 3500 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: 100 N. BROADWAY, STE. 970  
WICHITA, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 1270  
Production: Size 4.5 feet: 3466  
Liner: Size \_\_\_\_\_ feet:

\$113.75 4-230

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/27/2001 11:00 AM

Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.

Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (316) 265-3311

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Well was squeezed with annulus squeeze - TOC at 300'.  
4 1/2" liner squeezed from zero feet to 3466' with 268 sxs cement.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/27/2001 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH to 2400' - tied onto tubing and pumped 165 sxs cement and 600# hulls until cement circulated.  
Pulled out of hole - tied onto casing and pumped 5 more barrels and 20 more sxs cement pumped in Max. P.S.I. 800#. S.I.P. 500#.  
Tied onto backside and pumped 6 sxs into backside. S.I.P. 500#.

INVOICED

DATE 3-30-01  
INV. NO. 2001061549

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 29 2001  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY - TICKET #6532.

Plugged through: TBG

District: 04

100

Signed Pat Staab  
(TECHNICIAN)

Form CP-2/3  
40

MAR 27 2001

OKMAR OIL COMPANY

#1

WILES

16-11-19W 33

NE NE SE

Contr. GLENN R NYE DRUG COMPANY

ELLIS

County

E1959 RB

Comm.

Comp.

3-27-53

IP

388 BOPD

Tops	Depth	Datum
HEEB	3145	-1186
LANS	3186	-1227
CONG	3424	-1465
SIMP	3459	-1500
ARB	3496	-1537
TD	3500	-1541


Casing

8" 1270

5" 3497

CO 3500: ACID 500

SOLOMON POOL

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS