

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02258-00-00⁰¹
Spot: CSWSWSE Sec/Twnshp/Rge: 14-11S-19W
330 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: DEVINE A OWWO Well Number: 1
County: ELLIS Total Vertical Depth: 3473 feet

Operator License No.: 31430
Op Name: WHITE EAGLE RESOURCES CORP.
Address: 881 W. CHESTNUT CIRCLE
LOUISVILLE, CO 80027

Conductor Pipe: Size 13.375 feet: 0
Surface Casing: Size 8.625 feet: 1304 w/575 sxs cmt
Production: Size 5.5 feet: 3464 w/200 sxs cmt #112.87
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/18/2001 9:00 AM

Plug Co. License No.: 31430 Plug Co. Name: WHITE EAGLE RESOURCES CORP.

Proposal Rcvd. from: RANDY WEIGLE Company: WHITE EAGLE RESOURCES CORP. Phone: (785) 737-3736

Proposed Plugging Method: In preparation of welding 2" collar on 8 5/8" surface pipe, 5 1/2" casing fell down hole.
LK Wireline found 5 1/2" casing top at 612'.
Fluid level 650' with P.B.T.D. 1536'.
Ordered out 400 sxs 60/40 pozmix with 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/19/2001 9:30 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1500'.
LK Wireline perforated 5 holes at 1542'.
Allied pumped 275 sxs 60/40 pozmix - 10% gel. Lost circulation 30 bbl out.
Shut down 30 minutes - pumped 75 sxs - still no returns.
Shut in 20 minutes - pumped 50 sxs. Last 15 sxs started circulating.
Pulled tubing out of the hole.
June 19, 2001 - Ran tubing in and tagged cement at 402'.
Allied pumped 80 sxs with 500# hulls. Circulated cement.
PTOH. Squeezed with 10 sxs.
Max. P.S.I. 200#. S.I.P. 200#.
Total of 490 sxs with 500# hulls.

INVOICED
DATE 6-20-01
WEL. NO. 2001061969

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 20 2001
CONSERVATION DIVISION

Remarks: WELL SHOWN AS OWWO WAS A RE-COMPLETION. EMERGENCY PLUG ORDERS GIVEN WHILE RIG OVE

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

