

6-12

6090438

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-24.658-0000
NW /4 SEC. 14, 11 S, 19 W
3840 feet from S section line
3630 feet from E section line

Operator license# 3293
Operator: Russell Oil, Inc.
Address: P.O. Box 272
Russell, Kansas 67665

Lease Vine well # 1
County Ellis
Well total depth 3516 feet
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 254 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Shields Drilling Company, Inc. License# 5655
Address: Russell, Kansas 67665

Company to plug at: Hour: 1:20 PM Day: B Month: 6 Year: 1990

Plugging proposal received from: Burton Beery

Company: Shields Drlg. Co., Inc. phone:
Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 3500 feet with 20 sacks Rat hole: 15 sacks
2nd plug @ 1300 feet " 20 " Mousehole: 10 sacks
3rd plug @ 610 feet " 100 "
4th plug @ 300 feet " 40 "
5th plug @ 40 feet " wiper plug & 10sx

Plugging Proposal Received by: Ed Schumacher (KCC)
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:30 PM, Day: 12, Month: 6, Year: 1990

Actual plugging report: Hole reported plugged as above.
Order 215 sx 60/40 Pozmix w/ 6% gel and 2 sx celloflake or flowcel

Remarks: Elevation: 1960 GL, Anhydrite depth: 1284 -1329 feet

Did penetrate Arbuckle, cemented by Allied Cementing Company

INVOICED

Did observe the plugging.

Edwin A. Schumacher
Edwin A. Schumacher
(agent)

DATE 7-3-90
INV. NO. 28525

J. S.

1990