

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-02253-00-02

Spot: N2S2SW Sec/Twnshp/Rge: 10-11S-19W  
990 feet from S Section Line, 3960 feet from E Section Line

Lease/Unit Name: ALBERT

Well Number: 5

County: ELLIS

Total Vertical Depth: 3460 feet

Operator License No.: 5363

Conductor Pipe: Size feet:

Op Name: BEREXCO, INC.

Surface Casing: Size 8.625 feet: 178

w/170 sxs cmt

8112.45

Address: PO BOX 20380  
WICHITA, KS 67208

Production: Size 5.5 feet: 3504

w/150 sxs cmt

Liner: Size feet:

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/22/2002 10:00 AM

Plug Co. License No.: 5363

Plug Co. Name: BEREXCO, INC.

Proposal Rcvd. from: MARK LEIKER

Company: BEREXCO, INC.

Phone: (785) 628-6101

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.  
LKC 3230' - 3254'.  
Order shows top stage 600' with 150 sxs.  
Casing was bad.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 01/22/2002 12:30 PM

KCC Agent: PAT STAAB

**Actual Plugging Report:**

Berexo RIH with tubing to 3234' and pumped 40 sxs 60/40 pozmix with 200# hulls.  
Pulled tubing to 1320' and pumped 110 sxs 60/40 pozmix with 300# hulls to circulate cement.  
Pulled tubing and tied onto casing with a swedge and pumped 105 sxs 60/40 pozmix with Max. P.S.I. 700#. S.I.P. 400#.  
Backside was full of cement - visual inspection.

Remarks: ALLIED CEMENTING COMPANY - TICKET #10435.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

100

FEB 04 2002

INVOICED

DATE Feb 7-02

INV. NO. 2002061357

Form CP-2/3

OKMAR OIL

#5 ALBERT

10-11-19W  
N2 S2 SW

Contr. G-M-R

ELLIS County

E 1989RB Comm.

Comp. 11-25-55

IP 19 BOPD

Tops	Depth	Datum
ANH	1294	695
TOP	2935	-946
HEEB	3155	-1166
KC	3194	-1205
ARB	3503	-1514
TD	3507	-1518

Casing  
 8" 178 DST 2950-70/1 HR, 150'  
 5" 3504 ACID CM, 60' MDY WTR,  
 BHP 1010#: DST 3210-35/1 HR  
 90' O & GCM, 60' MDY OIL,  
 120' MDY WTR, BHP 550#  
 DST 3241-55/1/2 HR, 435' OIL  
 & MUD, BHP 490#: DST 3253-63/  
 1 HR, 10' H OCM, 30' OCM,  
 BHP 550#: DST 3272-78/40",  
 SOLOMON 200' SW, BHP 825#  
 DST 3339-65/40",  
 10' MUD: DD 3507  
 1 BOPH

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

10-11-19W  
 N2 S2 SW