

4-020044

2-18

15-05102257-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 01-17-57

SW SW NW /4 SEC. ¹⁰ ¹¹ ¹⁹ ~~03~~, ~~40~~ S, ~~11~~ W
feet from S section line
feet from E section line

Operator license# 05363

Lease: Falconberry "A" Well # 3

Operator: Berexco, Inc.

County: Ellis

Address: Box 723
Hays, Kansas 67601

Well total depth 3622 feet ^{117.71}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 3/4 Inch @ 221 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Berexco, Inc. License# 05363

Address: Box 723, Hays, Kansas 67601

Company to plug at: Hour: PM Day: 18 Month: February Year: 1994

Plugging proposal received from: Berexco, Inc.

Company: Berexco, Inc. Phone: 913/628-6101


Were: 8 3/4" surface casing @ 221' w/150 sx cmt; 5 1/2" production casing @ 3618' w/150 sx cmt; Elevation: 2086' G.L.; T.D.: 3622'; Anhydrite: 1420'; DV tool @ 1419' w/400 sx cmt; Casing squeezed @ 1010 w/150 sx cmt; Open hole: Arbuckle 3618-3622; 1080' fluid in hole;

Ordered 145 sx 60/40 pozmix w/10% gel, 200# hulls and 13 sx gel

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All , Part , None
Completed: Hour: 2:45p, Day: 18, Month: February, Year: 1994

Actual plugging report: Tied onto 8 3/4" surface casing and attempted to pump cmt. Surface casing pressured immediately. Tied onto 5 1/2" production csq. Pumped 25 sx cmt w/ 200 # hulls. Pumped 13 sx gel. Pumped 120 sx cmt. Maximum pressure: 1500#; End pressure: 1300#; Completion time: 2:45pm

Remarks: Allied Cement performed the cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2086 GL

I did / did not observe the plugging.  (agent)

INVOICED

DATE 3-11-94

INV. NO. 40087