

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6 020394

API NUMBER 15-05102252-0000

SW / 4 , SEC. 10 , T 11 S, R 19 (W)

_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Lease Name Albert Well # 2

Operator: Okmar Oil Co.

County Ellis 115.96

Name & Address 980 4th Financial Center

Well Total Depth 3568 feet

Wichita, Ks. 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 139

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Okmar Oil Co. License Number 5245

Address Same

Company to plug at: Hour: 8:30 AM Day: 1 Month: July Year: 1987

Plugging proposal received from George Jorgenson

(company name) Okmar (phone) _____

were: Order 250 sx Econolite and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Hole squeeze at 600' to surface

Shot hole Anhy. 1200'

Plugging Proposal Received by Gilbert Balthazor
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15AM Day: 1 Month: July Year: 1987

ACTUAL PLUGGING REPORT

1st plug at 2998 to 2038 w/45 sx Econolite

2nd plug at 2038 to 1778 w/45 sx

3rd plug at 1778 to surface with 60 sx

4th plug at 100 sx squeeze total 250 sx Max. Pressure 400 lbs, shut in 200 lbs

5th plug at annulus w/ no sks 300 lbs

Remarks: _____
(If additional description is necessary, use BACK of this form.)

It is to be observed this plugging.

INVOICED

DATE 7-21-87

INV. NO. 17537

Signed Gilbert Balthazor
(TECHNICIAN)
Gilbert Balthazor

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1987
CONSERVATION DIVISION
Wichita, Kansas